


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Butler County, Sec. 8 Twp. 26S Rge. 3E (E) (W)
Location as "NE/CNW/SE" or footage from lines C W/2 NW/4
Lease Owner Charles Gould
Lease Name Breneman Well No. 2
Office Address 5806 N. Broadway, Wichita, KS 67219
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well SWD *KCC RR*
Date well completed January 22 19 74
Application for plugging filed _____ 19 _____
Application for plugging approved _____ 19 _____
Plugging commenced January 17 19 74
Plugging completed January 22 19 74
Reason for abandonment of well or producing formation Non-Commercial



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2836 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Four (4) sacks cement from 2836 ft. to 2788 ft. Mud from 2788 ft. to 220 ft. Rock bridge from 220 ft. to 200 ft. Ten (10) sacks cement from 200 ft. to 150 ft. Mud from 150 ft. to 40 ft. Rock bridge from 40 ft. to 35 ft. Seven (7) sacks cement from 35 ft. to top.

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor El Dorado Supply Company
Address 764 Oil Hill Road, El Dorado, KS 67042



Kansas, COUNTY OF Butler, ss.
Debbie Brownrigg (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Debbie Brownrigg
750 Oil Hill Rd., El Dorado, Kansas
(Address)

Subscribed and Sworn to before me this 4th day of February, 19 74

My commission expires Dec. 12, 1976

Bonnie W. Zylor
Notary Public.

Company	Eureka Drilling Company and Charles Gould
Farm	Breneman
Well	#2
Location	C W/2 NW/4 Section 8-26S-3E Butler County
Elevation	1335 Ground level
Date	Commenced: November 8, 1970 Compoeted: November 16, 1970
Casing record	161 ft. of 7" surface
Contractor	Eureka Drilling Company Hamilton, Kansas Rig #3

0-90	soil and clay
167	lime w/shale strks
440	lime
930	shale w/lime strks
1335	shale w/lime strks
1630	lime w/shale strks
1660	lime and shale
1710	shale w/lime strks
1790	lime
2015	shale w/lime strks
2235	lime
2356	shale w/lime strks
2505	lime
2578	shale and lime
2620	shale w/lime strks
2640	shale
2710	lime
2791	shale w/lime strks
2824	lime, chert Mississippi
2836	lime, chert, shale
2836	R.T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 26 1973
 CONSERVATION DIVISION
 Wichita, Kansas