

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

API # 15-093-00149-00-02 KCC AB 8-22-08 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 4/20/55

Well Operator: XTO Energy, Inc KCC License #: 32864
(Owner / Company Name) (Operator's)

Address: 210 Park Ave., Ste. 2350 City: Oklahoma City

State: Oklahoma Zip Code: 73102 Contact Phone: (405) 232-4011

Lease: Finkelstein Well #: 2-1 Sec. 1 Twp. 23 S. R. 37 East West

C SE Spot Location / QQQQ County: Kearny

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10 3/4" Set at: 260' Cemented with: 250 Sacks

Production Casing Size: 7 7/8" Set at: 2647' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs @ 2533' - 43', 2548'-55', 2572'-96', & 2632'-44' CIBP @ 2480'

Elevation: 3210' (G.L. / K.B.) T.D.: 2650' PBDT: 2647' Anhydrite Depth: 2085' per ACO-1 dated 9/13/79
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Determine free point, cut and pull 5 1/2" casing. Run tbg & hydrite plug to +/- 1200' and pump 60 sx cmt. Pull tbg up to 361' and pump 125 sx cmt. Tag top of cmt. Pull tbg up to 60' and pump 40 sx cmt to surface. Dig out wellhead and weld on steel marker.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Littell & Mark Gosch RECEIVED
KANSAS CORPORATION COMMISSION

Address: P. O. Box 383 or 805 South Hwy 25 City / State: Lakin, KS 67860 Phone: (620) 355-7838 **JAN 14 2008**

Plugging Contractor: Holman Services KCC License #: 31705 CONSERVATION DIVISION
(Company Name) (Contractor's) WICHITA, KS

Address: P. O. Box 2742, Pampa, TX 79065 Phone: (806) 665-2550

Proposed Date and Hour of Plugging (if known?): Unknown at this time.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/11/07 Authorized Operator / Agent: Karen Byers (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

XTO ENERGY INC.
210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102-5683

March 25, 2008

Re: FINKELSTEIN #2-1
API 15-093-00149-00-00
1-23S-37W, 1320 FSL 1320 FEL
KEARNY COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 21, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,



Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888