

15-065-20428-00-00

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Nickelson Well No. 3

Location: NE-SE-NW Sec. 2 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4100' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Voth was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated.

4100'--4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 4071'. Top perforations from 3914' to 3918'.

Push plug to 3875', sand-back to 3850' and set # Sx. cement with dump Bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Sx. cement, staged.

Very truly yours,

Conservation Division Agent