

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 5 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Incorporated,

Complete Address: 815 Wichita Plaza, Wichita, Kansas.

Lease Name: Knoll Well No. 1

Location: SW-SE-SE Sec. 16 Twp. 10 Rge. (E)(W) 24

County Graham Total Depth 4015 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

210' -- 8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

"	"	210' with $\frac{1}{4}$ sk. hulls & 20 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls & 10 Sx. cement.

Very truly yours,

*A. D. Nichols*  
Conservation Division Agent