

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Art Budig of March Drilling Company has this

date requested permission to plug the following described well:

Rupe-Stoskopf

Mr. Budig guarantees payment of the plugging fee.

Operator's full Name: Rupe-Stoskopf,

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name: Brown Well No. 1

Location: NW-SW-NW Sec. 22 Twp. 10 Rge. (E)(W) 24

County Graham Total Depth 4022 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Budig was instructed to plug the well as follows:

180'--8 5/8" Surface pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

" " 180' with 1/4 sk. hulls & 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

Conservation Division Agent