

15-065-20211-00-00

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAR. 27 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. James Ehrlich of American Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Glen Rupe.

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name: Kline Well No. 1

Location: SW-SW-SW Sec. 22 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4000 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 100 Sx. cement thru DP. Pull DP to 220' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent