



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Burkhart of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Burkhart guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation.

Complete Address: 312 Union Center Building, Wichita, Kansas.

Lease Name: Gano Well No. 3

Location: CS/2-SE Sec. 2 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4056' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burkhart was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent