



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
CORPORATION COMMISSION  
MAY 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Box #370, Hays, Kansas.

Lease Name: J. Sproul Well No. 3

Location: NE-NE-SW Sec. 2 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4040' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Draper was instructed to plug the well as follows:

201'--8 5/8" Surface casing, cement circulated with--  
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*N. L. Nichols*  
Conservation Division Agent