

2 100564

1-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 015-21,577-00-00
SW, SEC. 18, T 26 S, R 3E W/E
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5446

Lease Name Lygrisse Well # 1

Operator: Ben Giles
Name & Address 321 E. William, #207
Wichita, KS 67202
316-265-1992

County Butler 94.90

Well Total Depth 2920 feet

Conductor Pipe: Size 4-1/2" feet 2919'/75 SX

Surface Casing: Size 8-5/8" feet 200'/115 SX

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated perf 2882-84' 2866-68' 2873-75'

Plugging Contractor McPherson Drilling License Number 5495

Address RR #2, Box 168D, Augusta, KS 67010

Company to plug at: Hour: 2:00p Day: 26 Month: 1 Year: 1990

Plugging proposal received from Bill McPherson

(company name) McPherson Drilling (phone)

were: Sand bottom to 50' above top perf - dump 5 sx cmt w/bailer - shoot & pull
4-1/2" - bail down to 300' & fill w/redimix

Plugging Proposal Received by Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00p Day: 26 Month: 1 Year: 1990

ACTUAL PLUGGING REPORT 2800' bridge plug with 15 gal rock & 4 sx cmt - shot and
pulled 2450' of 4-1/2" = pumped 90 sx cmt from top.

RECEIVED
STATE CORPORATION
2-15-90
FEB 5 1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: HOWCO #881676 90 sx 60/40 4% Oper PSI 300# SI 200#
(If additional description is necessary, use BACK of this form.)

I did ~~not~~ observe this plugging.

DATE 2-16-90

Signed J.L. Sanders
(TECHNICIAN)

INV. NO. 27496