

7-23 15-065-20430-00-00

194
R

4-062665

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-20,430-00-00
NE NW SW /4 SEC. 02, 10 S, 24 W
2310 feet from S section line
4290 feet from E section line

Operator license# 4767

Lease Sproul well # P-2

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market
Suite 1000
Wichita, Kansas 67202

Well total depth 4100 feet ^{133.25}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 205 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Box 347, Chase, Kansas 67524

Company to plug at: Hour: 9:30A.M. Day: 23 Month: July Year: 92

Plugging proposal received from: Mike Kelso and John Niernberger

Company: Ritchie Exploration, Inc. Phone: 913-628-2924

Were: Order 300 sks. of 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:00P.M., Day: 23, Month: July, Year: 92

Actual plugging report: 8 5/8" @ 205' w/160 sks. 4 1/2" @ 4887' w/225
sks. Top perf. @ 3836'. Plugged bottom with sand and 5 sks. cement to
3775'. Shot pipe 3 times and recovered 1600'. Pump in 4 1/2" casing
25 sks. cement followed with 5 sks. hulls in cement. Hooked on to
8 5/8" and circulated cement from 1550' to surface with 185 sks. with
500 P.S.I. Max. pressure on 4 1/2" - 500 P.S.I. Shut in @ 300 P.S.I.
Total sacks 185 cement.

Remarks:

Condition of casing(in hole):GOOD X BAD Anhy.plug:YES NO RECEIVED

Bottom plug(in place):YES X, CALC , NO Dakota plug:YES X CORPORATION COMMISSION

Plugged through TUBING , CASING X. Elevation: 1926 GL 7-29-92

I did X / did not [] observe the plugging.

Gilbert G. Scheck JUL 29 1992

DATE 8-6-92
INV. NO. 35860

CONSERVATION DIVISION
(agent) Wichita, Kansas
Form CP-2/3