

5-31

4-020007

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,709-0000

N/2 N/2NW /4 SEC. 16, 10 S, 24 W
330 feet from S section line
1320 feet from E section line

Operator license# 03655

Lease: Leo Dinkle Well # 1

Operator: Staab Energy & Leasing

County: Graham

Address: 2514 Haney Drive
Hays, Kansas 67601

Well total depth 4037 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 1/2 Inch @ 220 feet

131.20

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Shields Drilling, Inc. License# 5655

5655 RT REC

Address: 326 Main, P.O. Box 709, Russell KS 67665

Company to plug at: Hour: _____ Day: 31 Month: May Year: 1993

Plugging proposal received from: Burton Beery

Company: Shields Drilling, Inc. Phone: _____

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2145 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1250 feet with 100 sacks Mouse hole: 10 sacks

3rd plug @ 270 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:30, Day: 31, Month: May, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2489 GL

I did[] / did not[] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1993
6-7-93
CONSERVATION DIVISION
Wichita, Kansas
Form CP-2
(agent) Ken Kuhn

INVOICED

DATE 6-9-93
INV. NO. 32874