

6 100381

3-16

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22, 506-00-00

N/2 SW SE SEC. 22, T 10 S, R 24 W/E

990 feet from S section line
1980 feet from E section line

Lease Name Sproul Well # 1

County Graham 131.46

Well Total Depth 4045 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 207

TECHNICIAN'S PLUGGING REPORT

Operator License # 7448

Operator: Burch Exploration

Name & Address

11225 Edinborough Way

Parker, Colorado 80134

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Western Ks. Drilling License Number 4083

Address Hays, Ks. 67601

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Jim Manley

(company name) Western Ks. Drilling (phone) _____

were: Spot through drill pipe w/heavy mud between all plugs.

1st plug at 2060' w/25 sks

2nd plug at 1210' w/100 sks

3rd plug at 250' w/40 sks

4th plug at 40' w/wiper plug and 10 sks

rathole 15 sks Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:00 AM Day: 16 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT Hole reported plugged as above.

Order 190 sks 60/40 Poz w/6% Gel and 2 sks celloflake/flocele.

Elevation: 2436' Anhydrite depth 2057' - 96'

Remarks: Did not penetrate arbuckle Cemented by Halliburton
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 5-15-89

INV. NO. 24848

MAY 31 1989

Signed David K. Wann (TECHNICIAN)

Rec 5-15-89
KCC