

6010086

3 KCC af B

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- ~~162~~-22346-00-00

SW, Sec. 16, T 9 S, R 18 W/2

2970 feet from N/4 section line

330 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5114

Lease Name Stahl Well # 1

Operator: National Development Co.
Name & Address 205 E. Central
Wichita Ks.

County Rooks

Well Total Depth 3575 feet

Conductor Pipe: Size feet 116.19

Surface Casing: Size 8 7/8 feet 273

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Duke Drlg. Co. License Number 5929

Address Box 823 Great Bend Ks.

Company to plug at: Hour: 3 AM Day: 22 Month: 4 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Leonard Williamson

(company name) Duke Drlg Co. (phone) 376 793 8366

were: order 185 sx. cement 50/50 formix 6% gel 3% cal. cl.

1 sx. hulls 1-8 7/8 plug 1 sx. Flow Seal

Heavy mud between all plugs

Pump cement down drill pipe.

Elev. - 2095 Anhydrite 1446-85 Arbuckle No

Dakota- 1500
595 = 900

Signed Dale F. Batthayor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 AM Day: 22 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1450 for 20 mi.

25 sx @ 1450

100 sx @ 900 mixed w/ 1 sx. Flow Seal

40 sx @ 320, 1 sx hulls pushed plug to 40'

10 sx @ 40

10 sx in Rat hole

Remarks:

cementing to Allied

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1984

CONSERVATION DIVISION
Wichita, Kansas

4-30-84

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Dale F. Batthayor
(TECHNICIAN)

INVOICED

DATE 5-1-84

INV. NO. 1323

FORM CP-2/3
Rev. 9-82