

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22162-00-00
Spot: E2E2SW Sec/Twnshp/Rge: 4-28S-5W
1320 feet from S Section Line, 2310 feet from W Section Line
Lease Name: RAMSDALE Well #: 3-4
County: KINGMAN Total Vertical Depth: 3950 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	264		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/22/2008 6:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: LOU Company: SOUTHWIND DRILLING INC Phone: (620) 564-3800

Proposed Plugging Method: 35 SKS ARB. 35 SKS 850, 35 SKS 450, 35 SKS 315, 25 SKS 60, 20 SKS RH

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 08/22/2008 9:22 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE DRL PIPE WAS RUN OPEN END TO 850, WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 450, WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 315, WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 60', WHERE 25 SKS OF CMT WAS CIRCD TO SURFACE. THE RAT HOLE WAS CIRCD WITH 20 SKS OF CMT.

Perfs:

INVOICED

DATE 9/14/08
INV. NO. 2009060368

Remarks: BASIC ENERGY 18731 60/40 4% GEL

Plugged through: DP

District: 02

RECEIVED
KANSAS CORPORATION COMMISSION

Signed _____

(TECHNICIAN)

SEP 02 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3