

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20894-00-00
Spot: NESENE Sec/Twnshp/Rge: 30-19S-6E
1650 feet from N Section Line, 330 feet from E Section Line
Lease Name: PANTHER RANCH Well #: 1
County: CHASE Total Vertical Depth: 2246 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2246		185 SX CMT.
SURF	8.625	240		140 SX CMT. \$ 73.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2008 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFO AND CAP WITH 4 SXS CEMENT. CIRCULATE WITH CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: NONE
Date/Time Plugging Completed: 08/21/2008 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2135' AND CAPPED WITH 4 SXS CEMENT. CUT PIPE AT 800' AND PULLED. BALED FLUID TO 300'. DUMPED 5 YRDS SLURRY MIX TO FILL FROM 300' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2185	2195		

INVOICED
DATE 09/16/08
INV. NO. 2009060380

Remarks: CONCRETE PRODUCTS (HILLSBORO) TICKET #44276 TOTAL = 5 YDS SLURRY MIX SLURRY MIX = 22 SXS PER YD

Plugged through: CSG

District: 02

RECEIVED
KANSAS CORPORATION COMMISSION

Signed

Greg Eves

(TECHNICIAN)

SEP 02 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3