

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21333-00-00
Spot: NWSESW Sec/Twnshp/Rge: 10-19S-1E
747 feet from S Section Line, 3577 feet from E Section Line
Lease Name: PENNER A Well #: 3
County: MARION Total Vertical Depth: 2833 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N MARKET ST STE 1120
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2833		185 SX
SURF	8.625	283		166 SX

#92.07

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2008 11:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 4 SXS CEMENT. CIRCULATE TO SURFACE FROM 340'.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 08/20/2008 11:55 AM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2766' AND CAPPED WITH 4 SXS CEMENT. CUT AND PULLED 1400' OF 4 1/2" CASING. BALED FLUID TO 350'. DUMPED 5 YDS SLURRY MIX TO FILL FROM 350' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2816	2822		

INVOICED
DATE 09/16/08
INV. NO. 2009060380

Remarks: CONCRETE PRODUCTS (HILLSBORO) TICKET #44266 TOTAL = 5 YDS SLURRY MIX SLURRY MIX = 22 SXS CEMENT PER YARD.

Plugged through: DP

District: 02

RECEIVED
KANSAS CORPORATION COMMISSION

Signed

Greg Eves

(TECHNICIAN)

SEP 02 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3