

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20817-00-00
Spot: SENENWNW Sec/Twnshp/Rge: 22-13S-32W
601 feet from N Section Line, 1219 feet from W Section Line
Lease Name: GLASSMAN Well #: 3-22
County: LOGAN Total Vertical Depth: 4710 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 W MAIN ST
SALEM, IL 62881

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		160 SX

153.08

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/23/2008 3:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: SHAKESPEARE OIL CO., INC. Phone: (618) 548-1585

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE WitnessType: NONE
Date/Time Plugging Completed: 07/23/2008 5:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

1st. Plug at 2495' w/25 sxs.
2nd. Plug at 1460' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

INVOICED

DATE 09/16/08
INV. NO. 2009060384

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 28 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

Form CP-2/3

AUG 22 2008

Handwritten initials