

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21155-00-00  
Spot: NENENE Sec/Twnshp/Rge: 23-17S-18W  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: SCHWINDT FARMS Well #: 1  
County: RUSH Total Vertical Depth: 3680 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| PROD   | 4.5   | 3669       | 2035        | WITH 275 SX CMT |
| SURF   | 8.625 | 1219       |             | WITH 425 SX CMT |

119.60

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/04/2008 8:00 AM  
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE  
Proposal Rcvd. from: RON GEIST Company: GEIST, RON DBA WILDCAT WELL Phone: (785) 728-2040

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 08/04/2008 10:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SAND BACK TO 3126' & 4 SX CMT. 1ST PLUG PUMP 10 SX GEL & 50 SX CMT AT 1219'. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40-0' WITH 30 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3551 | 3557 |      |          |
| 3531 | 3535 |      |          |
| 3397 | 3401 |      |          |

**INVOICED**  
DATE 09/16/08  
INV. NO. 2009060389

RECEIVED  
KANSAS CORPORATION COMMISSION


**AUG 27 2008**

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

CONSERVATION DIVISION  
WICHITA, KS

District: 01



Signed Steve Durrant  
(TECHNICIAN)