

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21733-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 28-16S-16W  
990 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: ANDRE Well #: 1  
County: RUSH Total Vertical Depth: 3575 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3495		
PROD	4.5	3574	1603	WITH 200 SX CMT 116.19
SURF	8.625	1066		WITH 450 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/21/2008 9:00 AM  
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE  
Proposal Rcvd. from: RON GEIST Company: GEIST, RON DBA WILDCAT WELL Phone: (785) 728-2040

Proposed Plugging Method: SAND TO 3165' & 4 SX CMT. PLUG AT 1090' WITH GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/21/2008 10:10 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SAND TO 2550' & 4 SX CMT WITH BAILER. NOTE: SAND BRIDGED OFF HIGH PRESSURED IT DOWN AT 2500 PSIG. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1090' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3540	3541		
3426	3430		
3412	3415		
3392	3396		
3248	3251		
3215	3218		

INVOICED


DATE 09/16/08  
INV. NO. 2009060389

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 25 2008  
CONSERVATION DIVISION  
WICHITA KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)