

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19169-00-01
Spot: NENENE Sec/Twnshp/Rge: 17-11S-18W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: FRISBIE G Well #: 1
County: ELLIS Total Vertical Depth: 3586 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3585	0	200 SX
SURF	8.625	1273	0	700 SX

116.55

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2008 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 700# hulls.
Shoot perfs at 150' - 650' - 1250' - 1850'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2008 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in to 2892' - pumped 8 sxs gel - 50 sxs cement with 200# hulls.
Pulled tubing to 1857' - pumped 250 sxs cement - good circulation out of 5 1/2".
Pulled tubing out - tied onto top - pumped 150 sxs down casing - good circulation out the 8 5/8".
Everything full.

Perfs:

Top	Bot	Thru	Comments
3215	3432		
3151	3154		
3136	3139		
3114	3117		
2974	2980		

INVOICED

DATE 9-16-08
INV. NO. 2009060391

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 22 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #2148.

Plugged through: TBG

District: 04

Signed

Marvin Mills

(TECHNICIAN)

CM

Form CP-2/3

AUG 21 2008

PKS

ROBERT R. PRICE OPERATING, INC.

P.O. BOX 45442

TULSA, OK 74147

#1 "G" FRISBIE 'OWWO'

17-11-12W
NE NE NE


CONTR RANGER DRLG. CO., INC.

CTY ELLIS

GEOL

FIELD

WC(1/8 S OF COCHRAN;
SEP BY DRY HOLES)



ELV 1961 KB SPD 3/13/83
1956 GL

CARD ISSUED 7/7/83

IP P 7 BO & 67 BWPD

SHAW 2974-3185

LKC 3186-3432 OA

API NOT ASSIGNED

SMP	Tops	Depth/Datum
ANH	1262+ 699
TOP	2945- 984
HEEB	3170-1209
TOR	3188-1227
LANS	3212-1251
BKC	3437-1476
CONG	3469-1508
ARB	3542-1581
OTD	3574-1613
DDTD	3586-1625

OLD INFO: OPERATOR WAS PHILLIPS PETROLEUM COMPANY, #1 JOHN HANCOCK, SPD 5/26/43, SET 8" 1273, COMP. AS D&A 6/25/43, CONTR: UNKNOWN

SH DEAD OIL 3546-3549
NO DST'S

NEW INFO: FR 3/15/83, RE-ENTERED ON 3/13/83, WSH DWN TO OTD, DD 3586 TD, SET 5 1/2 " 3585/200SX: MICT - CO, PF (SHAW) 2974-3185 (EST) & PF (LKC) 3186-3432 (EST) OA W/1 SPF, AC 31,750G, SWB PT LD, GSO, POP, P 7 BO & 67 BWPD (GR 31"), 6/8/83, COMMINGLED - NO OTHER INFO TO BE RE-LEASED AT PRESENT

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS