

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23464-00-00
Spot: S2SENE Sec/Twnshp/Rge: 13-11S-19W
2970 feet from S Section Line, 660 feet from E Section Line
Lease Name: ALLISON B Well #: 4
County: ELLIS Total Vertical Depth: 3530 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3520	0	125 SX CMT
SURF	8.625	284	0	180 SX CMT

114.73

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2008 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 300# hulls.
Hole bridged off at 1589'.
Shoot perfs at 1270' - 585' - 335'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2008 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in to 1529' - pumped 75 sxs cement with 150# hulls.
Pulled tubing to 750' - pumped 120 sxs cement - good circulation of cement and 100# hulls.
Pulled tubing out - tied on top - squeezed with 40 sxs cement on 5.1/2" and 50# hulls.
Max. P.S.I. 400#. S.I.P. 175#.
Checked backside - full of cement.

Perfs:

Top	Bot	Thru	Comments
3412	3460		
3166	3392		
2901	3126		

INVOICED
DATE 9-16-08
INV. NO. 0009060391

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 25 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #2150.

Plugged through: TBG

District: 04

Signed CM
(TECHNICIAN)

CM

Form CP-2/3

AUG 21 2008

PKT

REPLACEMENT CARD

PETRO-DYNAMICS CORPORATION

255 N. WOODLAWN, #207, BLDG. #1

WICHITA, KS 67208

CONTR KANDRMLCO, INC.

#4 ALISON


13-11-19W

C S/2 SE NE

CTY ELLIS

GEOL _____

FIELD COCHRAN WEST



ELV 1922 KB SPD 5/16/83 CARD ISSUED 8/11/83 IP P 55 BO & 150 BWPD

1914 GL LANS 3202-3388 OA
API 15-051-23,464 (NEW PAY-CONG) CONG 3415-3440 OA

LOG	Tops	Depth/Datum
ANH	1264 + 658
HEEB	3128-1206
LANS	3167-1245
SWOPE	3363-1441
BKC	3404-1482
CONG	3426-1504
RTD	3530-1608

8 5/8 " 281/180SX; 4 1/2 " 3528
 DST (1) 3187-3216 (LKC) / TIMES NA, REC 65' MUD, W/OIL SPTS, SIP 988-945#, FP 45-56 / 68-70#
 DST (2) 3314-56 (LKC) / TIMES NA, 250' GIP, REC 60' HOGMC (50% OIL, 45% MUD, 5% WTR), 70' GSY MO (60% OIL, 35% MUD, 5% WTR), SOME FO ON TOP OF TOOL, SIP 1011-988#, FP 68-79 / 79-102#
 DST (3) 3356-78 (LKC) / TIMES NA, REC 20' MUD, W/TR OIL, SIP 795-500#, FP 45-45 / 45-45#
 DST (4) 3426-60 (CONG) / TIMES NA, REC 15' CL OIL, 45' OCM, SIP 1045-1000#, FP 56-56/ 56-68#
 DST (5) 3472-84 (CONG) / TIMES NA, REC 240' MW, W/TR OIL, 910' SW, W/SPTS OIL, SIP 1045-1011#, FP 56-250 / 306-488#
 MICT - CO, PF (CONG) / 3415-20, W/1 SPF, 3426-40, W/1 SPF, SWB DWN, SO, PF (LKC) 3336-40, W/2 SPF, 3384-88, 3240-58, 3202-06, W/2 SPF, SWB LD, R & T, POP, P 55 BO & 150 BWPD, 8/8/83

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

NOTE: CORRECTION 6/30/83 - ORIGINALLY FIRST REPORTED IN C S/2 NE