

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23687-00-00
Spot: NENENE Sec/Twnshp/Rge: 13-11S-19W
4840 feet from S Section Line, 330 feet from E Section Line
Lease Name: ALLISON B Well #: 7
County: ELLIS Total Vertical Depth: 3555 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3552	0	200 SX
SURF	8.625	1310	0	350 SX

115.54

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2008 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2008 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3500' - pumped 50 sxs cement with 100# hulls.
Pulled tubing to 3004' - pumped 11 sxs gel.
Pulled tubing to 1967' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1052' - pumped 115 sxs cement with 200# hulls - good circulation of cement.
Pulled tubing out - topped off with 55 sxs cement.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3448	3522		
2962	3428		

INVOICED
DATE 9-16-08
INV. NO. 2009060391

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 22 2008

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #2145.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN)

CM

Form CP-2/3

AUG 20 2008

PKT

SEAHAWK OIL INTERNATIONAL, INC.
660 NEWPORT CENTER DR., #750

#7 ALISON

13-11-19W
110's


NEWPORT BEACH, CA 92660
CONTR KANDRILCO, INC.

CTY ELLIS

C NE NE NE

GEOL

FIELD COCHRAN WEST



ELV 1954 KB SPD 11/21/83 CARD ISSUED 5/10/84

IP P 20 B0 & 151 BWPD

1946 GL
API 15-057-23,687

SHAW 2962-?
LKC 3204-?
ARB 3448-?

LOG	Top	Depth/Datum
HEEB	3160-1206
LANS	3204-1250
BKC	3428-1474
ARB	3540-1586
RTD & LTD	3555-1601

8 5/8 " 1310 / 450SX; 5 1/2 " 3552 / 200SX
NO DSTS
MCT - CO, PF (PENN) 3448-?, W / 1-2 SPF, AC 750G (15% MCA), SWB DWN, GSO, PF (SHAW) 2962-?, W / 1-2 SPF, ACIDIZED (15% MCA), SWB DWN, GSO, PF (LKC) 3204-?, W / 1-2 SPF, ACIDIZED (15% MCA), SWB DWN, GSO, SET 2 7/8 " TBG AT 3525', POP, P 20 B0 & 151 BWPD, 2/7/84, COMMINGLED - NO OTHER INFO RELEASED BY OPERATOR CONCERNING SELECTED PF INTV'S

NOTE: CORRECTION 12/15/83 - ORIGINALLY FIRST REPORTED IN 190'E, C E/2 E/2 NE

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS