

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21573-00-00  
Spot: SWNENENE Sec/Twnshp/Rge: 36-26S-17W  
500 feet from N Section Line, 500 feet from E Section Line  
Lease Name: CROCKETT Well #: 5-36  
County: EDWARDS Total Vertical Depth: 412 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 155 N MARKET STE 700  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	349		WITH 425 SX CMT INTIAL

35

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2008 9:30 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: PAT LIVINGSTON Company: VINCENT OIL Phone: (316) 262-3573

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/13/2008 9:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

**\*\*FAILED SURFACE PIPE JOB. CMT FAILED TO CIRCULATE ON PRIMARY JOB. RAN 1" TBG TO 190' PUMPED 100 SX CMT. RAN 1" TO 149' PUMPED 100 SX CMT. RAN 1" TO 50' PUMPED 200 SX CMT.\*\* 8/12/08 FOUND CMT TOP INSIDE 8 5/8" AT 294'. DRILLED DOWN TO 319'. LAST 10' HARD CEMENT. RAN TBG TO 290'. CIRCULATED CMT TO SURFACE WITH 50 SX CMT. PULLED TBG TOPPED OFF 8 5/8" WITH 5 SX CMT.**

Perfs:

**INVOICED**  
DATE 9-16-08  
INV. NO. 2009060392

RECEIVED  
KANSAS CORPORATION COMMISSION  
**AUG 27 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
AUG 18 2008  
KCC Dodge City

Signed Richard M. Lacey  
(TECHNICIAN)