

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED

2-16-70

FEB 16 1970

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsay of Cities Service Oil Company, has this date requested permission to plug the following described well:Mr. Lindsay guarantees payment of the plugging fee.Operator's full Name: Cities Service Oil Company,Complete Address: Box #553, Russell, Kansas.Lease Name: McPherson Well No. A-3Location: CS/2-SW-NE Sec. 4 Twp. 9 Rge. (E)(W) 23County: Graham Total Depth 3764' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Lindsay was instructed to plug the well as follows:203'--8 5/8" Surface casing, cement circulated with 125 Sx.
3764'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug back. Top perforations from 3750' to 3747'.Push plug to 3600', build sand bridge and set 5 Sx. cement with DB.
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,


 Conservation Division Agent