

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
2-16-70
FEB 16 1970CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsay of Cities Service Oil Co., has this
date requested permission to plug the following described well:Mr. Lindsay guarantees payment of the plugging fee.Operator's full Name: Cities Service Oil Company,Complete Address: Box #553, Russell, Kansas.Lease Name: McPherson Well No. A-2Location: CNW-SE Sec. 4 Twp. 9 Rge. (E)(W) 23County: Graham Total Depth 3825' Oil Well Gas Well Input Well SWD Well X D & A Lost Hole Mr. Lindsay was instructed to plug the well as follows:229'--8 5/8" Surface casing, cement circulated
3823'--5 1/2" Production casing, no info. of cement on bottom. Top perfor-
ations from 3714' to 3719'.Run 2" tubing to bottom of well and displace 25 Sx. cement thru tubing,
let cement set, pull available 5 1/2" casing and squeeze well thru 8 5/8"
casing with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

Conservation Division Agent