

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-19-70
FEB 19 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsay of Cities Service Oil Company, has this date requested permission to plug the following described well:

Mr. Lindsay guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box #553, Russell, Kansas

Lease Name: McPherson Well No. A-9

Location: NE-NE-SE Sec. 4 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 4250' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lindsay was instructed to plug the well as follows:

???--8 5/8" Surface casing, cement circulated.
4220'--5 1/2" Production casing cemented on bottom with 250 Sx. and with
450Sx. thru DV Tool set in the Anhydrite. Well plugged back to 3734'.
Top perforations from 3704' to 3710'.

Push plug to 3500', sand back to 3470' and set 5 Sx. cement with dump
Bailer. Pull available 5 1/2" casing and squeeze well with 20 sacks gel
and 115 Sx. cement, staged.

Very truly yours,

N. L. Nichols
Conservation Division Agent