

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1974
9-30-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: C. Fountain Well No. W-1

Location: 50' FNL & 50' FWL of NE/4 Sec. 5 Twp. 9 Rge. (E)(W) 23

County: Graham Original TD --3900'
Total Depth -2962' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole XXX

Mr. Niernberger was instructed to plug the well as follows:

102'--10 3/4" Surface casing, cement circulated with 175 Sx.
3899'--7" OD casing cemented on bottom with 150 Sx. 7" perforated @
1775' and cement circulated to surface. (7" CASING COLLAPSED @ 2950').

Run 3 1/2" DP to 2950' and displace 25 Sx. cement plus 6% gel thru DP,
Pull DP to 100' and run 25 Sx. cement plus 6% gel thru DP. Pull DP,
set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to base of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent