

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS, 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Reiter of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee.

Operator's full Name: Isern-Wells

Complete Address: Box #486, Ellinwood, Kansas.

Lease Name: Jones Well No. 1

Location: CN/2-NE-SE Sec. 5 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3815' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reiter was instructed to plug the well as follows:

221'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent