

RP

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
6-11-71  
JUN 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drlg., Co., Inc. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated.

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Engleman Well No. 1

Location: NE-NW-NE Sec. 8 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3840' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

259'--8 5/8" Surface casing, cement circulated with 175 Sx.  
top of Dakota section @ 800'.

Circulate hole with heavy mud. Pull DP to 1025' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Dickels  
Conservation Division Agent