

State of Kansas



State Corporation Commission

CONSERVATION DIVISION


(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1974
3-7-74
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this
date requested permission to plug the following described well:Mr. Kelso guarantees payment of the plugging fee.Operator's full Name: Don E. Pratt.Complete Address: Drawer #370, Hays, Kansas.Lease Name: Casey Jones Well No. 3Location: SW-SW-NE Sec. 11 Twp. 9 Rge. (E)(W) 23County: Graham Total Depth 3860' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Kelso was instructed to plug the well as follows:226'--8 5/8" Surface casing, cement circulated with 175 Sx.
3857'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug-
back nor perforations indicated.Push plug to 3450' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,


 Conservation Division Agent