

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
6-21-71
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: C. Jones Well No. 2

Location: SW-NW-NE Sec. 11 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3872 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

164'--8 5/8" Surface casing, cement circulated.

3864'--4 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3850'. Top perforations from 3820' to 3800'.

Sand well back to 3775' and set 3Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 135 Sx. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent