



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

3-7-74
MAR 7 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt.

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Casey Jones Well No. 6

Location: SW-NE-NE Sec. 11 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3891' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

154'--8 5/8" Surface casing, cement circulated with 130 Sx.
3878'--4 1/2" Production casing cemented on bottom with 300 Sx. 4 1/2" has
been squeezed with 125 Sx. cement thru perforations from 3678' to 3682'.
Perforations from 3805' to 3809'.

Sand well back to 3750' and set 5 Sx. cement with dump bailer. Pull 4 1/2"
casing and squeeze well with 5 sacks hulls, 25 sacks gel and 170 Cu. Ft.
cement, staged.

Very truly yours,

N. L. Orshel
Conservation Division Agent