



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1971  
CONSERVATION DIVISION  
Wichita, Kansas

11-15-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-30139-00-01

Dear Sir:

Mr. Gus Tarbach of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Tarbach guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources,

Complete Address: 1000 Century Plaza, Wichita, Kansas.

Lease Name: McElroy Well No. 1

Location: SE-NW-NE Sec. 4 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3860' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Tarbach was instructed to plug the well as follows:

228'--8 5/8" Surface casing, cement circualted .  
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 100 Sx.  
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent