



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1971
CONSERVATION DIVISION
Wichita, Kansas
01-13-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20404-00-00

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation,

Complete Address: 1000 Century Plaza, Wichita, Kansas.

Lease Name: McElroy Well No. 1

Location: SW-NE-NE Sec. 4 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3860' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 760'.

Circulate hole with heavy mud. Pull DP to 985' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. G. Nichols
Conservation Division Agent