



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-065-20320-00-01

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
12-10-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Don Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Sandlin Well No. 1

Location: SE-NW-NW Sec. 5 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3855' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

202'--8 5/8" Surface casing, cement circulated with 185 Sx.  
3854'--4 1/2" Production casing cemented on bottom with 125 Sx. Top of cement @ 3295' (Temp. Survey). Well plugged back to 3813'. Top perforations @ 3630'.

Push plug to 3600', sand back to 3575' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

A. L. Nichols  
Conservation Division Agent