

9-5

4-070058

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 8-19-57
NW ^{KCC NR} /4 SEC. 04, 09 S, 23 W
990 feet from S section line
3630 feet from E section line

Operator license# 5088
Operator: John J. Darrah
Address: 225 N. Market - Suite #300
Wichita, Kansas 67202

Lease: Brush Creek Unit Well # 107
County: Graham 124.74
Well total depth 3838 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 220 feet
W/175 sxs.

ABAND. oil well , Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: D.S. & W. Well Service License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525-0231

Company to plug at: Hour: 8:00 A.M. Day: 05 Month: September Year: 1997

Plugging proposal received from: John J. Darrah Jr.

Company: John J. Darrah Phone: 316-292-2095

Were: Tubing left in hole top of fish 2300'. Run tubing and circulate cement. Pull tubing and squeeze with cement. Check backside of 5 1/2". 5 1/2" @ 3838' w/125 sxs. Ordered 350 sxs 60/40 pozmix - 10% gel with 600# hulls.

RECEIVED
SEP 15 1997
9-15-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 4:00 P.M., Day: 05, Month: September, Year: 1997

Actual plugging report: Ran tubing to 2200'. Allied (Oakley) pumped 200 sxs 60/40 pozmix - 10% gel w/400# hulls. Did not break circulation. Shut down well on vacuum and pulled tubing to 1000'. Fluid on backside of tubing 250' from surface. Allied pumped 20 sxs - no returns. Pulled to 500'. Shut in 2 hrs. Pumped 100 sxs w/200# hulls. Still no returns. Pulled tubing out of hole, small vacuum. Pumped 60 sxs on backside. No pressure - shut in. Waited on cement truck 2.5 hrs. Pumped 100 sxs with 400# hull. No vacuum. Shut in 30 mins. Mixed 100 sxs with 100# hulls. No pressure. Cleared valve at 5 1/2" casing and shut in. Total 490 sxs down casing with 1100# hulls and 60 sxs on backside.

Remarks: Will check cement top 09-08-97 with wireline.

Condition of casing(in hole): GOOD _____ BAD Anhy.plug: YES NO _____
Bottom plug(in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ Elevation: 2311 GL

I did / did not [] observe the plugging.

Richard Williams
(agent)

INVOICED

DATE 9-16-97
INV. NO. 49010
9-5