

9-10

15-065-02804-00-00

4-070061

TO:

API Number: 15- - 10-25-57

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE NW SW /4 SEC. 04, 09 S, 23 W
1650 feet from S section line
4290 feet from E section line

Operator license# 5088

Lease: Brush Creek Unit Well # 108

Operator: John J. Darrah

County: Graham 123.44

Address: 225 N. Market - Suite #300
Wichita, Kansas 67202

Well total depth 3798 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 216 feet

ABAND. oil well , Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: D.S. & W. Well Service License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525-0231

Company to plug at: Hour: 9:00 A.M. Day: 10 Month: September Year: 1997

Plugging proposal received from: John J. Darrah Jr.

Company: John J. Darrah Phone: 316-292-2095

Were: Emergency plug with rig over hole. 5 1/2" casing at 3798'. Bad condition.
Ordered 350 sxs 60/40 pozmix - 10% gel with 800# hulls.
Cut slots at 2000' - 1150' - 275'. Circulate thru tubing and squeeze.

RECEIVED
KANSAS CORP COM
SEP 17 12:03
9-17-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:00 P.M., Day: 10, Month: September, Year: 1997

Actual plugging report: Cut slots in casing at 2000' - 1150' - 275'. Ran tubing to 2200'.
Circulated cement. 225 sxs 60/40 pozmix - 10% gel with 700# hulls. Pulled tubing out of
hole. Allied mixed 75 sxs. Max. P.S.I. 100#. S.I.P. 0#. Hooked-up to backside 8 5/8" and
pumped 50 sxs with 100# hulls. Max. P.S.I. 200#. S.I.P. 100#.

Remarks:

Condition of casing(in hole): GOOD _____ BAD Any plug: YES NO _____
Bottom plug(in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ Elevation: 2262 GL

I did / did not observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE 9-23-97
INV. NO. 49078