

4-032414

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-065-21,243-00-01

C W2 SE SW      /4 SEC. 05 , 09 , 23 W  
660 feet from S section line  
3630 feet from E section line

Operator license# 9615  
Operator: Joe Gerstner  
Address: RR 1 - Box 115A  
Ness City, Kansas 67560

5/16

Lease: Engleman Well # A-2  
County: Graham 126.43  
Well total depth 3890 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 265 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: P.M. Day: 16 Month: May Year: 2000

Plugging proposal received from: Rick Schreiber

Company: Joe Gerstner Phone:     

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Order work string of tubing.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 1 2000  
6-1-00  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [      ], None [      ]

Completed: Hour: P.M., Day: 16 Month: May, Year: 2000

Actual plugging report: 8 5/8" set at 265' w/170 sxs cwc. 4 1/2" set at 3889' w/125 sxs.  
Prod perms 3693' - 3712'. Holes in casing in Cedar Hill. Fish at 1340'+. Ran tubing to  
fish, mixed and pumped cement to circulate. Lay down tubing. Squeezed 4 1/2" with total 200  
sxs cement blend with 500# hulls mixed into Max. P.S.I. 300#. Held. Squeezed 8 5/8" with  
50 sxs cement blend to Max. P.S.I. 300#. Held. Plug complete.

Remarks:       
Condition of casing(in hole): GOOD      BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING     . Elevation:      GL

I did [ X ] / did not [      ] observe the plugging.

Carl Goodrow  
(agent)

INVOICE  
DATE 6/6/00  
INV. NO. 61823

Form CP-2/3

(R)