

4-032415

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-20,680-100-01

C N2 NE SE /4 SEC. 05 , 09 , 23 W
2310 feet from S section line
660 feet from E section line

010 E 17655

Operator license# 9615

N.W. E 26,321

Lease: Fountain-Jones Well # 1 OWWO

Operator: Joe Gerstner

County: Graham

123.99

Address: RR 1 - Box 115A
Ness City, Kansas 67560

5/16

Well total depth 3815 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 280 feet

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: A.M. Day: 16 Month: May Year: 2000

Plugging proposal received from: Rick Schreiber

Company: Joe Gerstner Phone:

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 2000
6-1-00
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:15 A.M., Day: 16 Month: May, Year: 2000

Actual plugging report: 8 5/8" set at 280' w/150 sxs cwc. 4 1/2" set at 3843' w/175 sxs. Prod perfs 3737' - 3777'. No information on backside - cement required critical area control shots at 1185' and 1900'. However, the backside squeeze pressured up to 600# immediately indicating a previous cement to surface compliance job. Squeezed 4 1/2" with 225 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 600#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

INVOICE L100
DATE 6/6/00
INV. NO. 61823

Form CP-2/3

