

8-26

15
R

4-031745

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-00575-00-01

SE NE SE /4 SEC. 05, 09 S, 23 W
1650 feet from S section line
330 feet from E section line

Operator license# 4767

Lease Reed Jones well # P-1

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market
#1000
Wichita, Kansas 67202

Well total depth 3830 feet / 24.47
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Chase, Kansas

Company to plug at: Hour: P.M. Day: 26 Month: August Year: 92

Plugging proposal received from: Manny

Company: Kelso Casing Pulling, Inc. Phone: _____

Were: 8 5/8" set @ 211' w/150 sx. cwc. 4 1/2" set @ 3828' w/125 sx.
P.B.T.D. 3740'. Perf. 3616' - 3717'. Order 250 sx. 65/35 pozmix
- 10% gel. - 500# hulls. B.J. Services.
Order sand and 4 sx. common cement. Pull pipe.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 6:45 P.M., Day: 26, Month: August, Year: 92

Actual plugging report: Sand back to 3554' w/4 sx. common cement on sand with bailer. Free point and shoot @ 2250'. Loaded 4 1/2" with cement slurry 70 sx. Laid down casing squeezed 8 5/8" with total of 180 sx. cement blend with 400# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 700#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL _____

I did[] did not[] observe the plugging.

DATE 4-29-92

INV. NO. 36265

Carl Goodrow

(agent)

RECEIVED
STATE CORPORATION COMMISSION
7-16-92
SEP 16 1992
CONSERVATION DIVISION
Wichita, Kansas