

PLUGGED

6 070446

API NUMBER 15-

To: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING SECTION C-NE-NW, SEC. 8, T. 9 S, R. 22

TECHNICIAN'S PLUGGING REPORT 5364 Beren Corp 7-14-08 feet from S section line

Operator License # 5245 Corp Loose Name STEWART Well # 2-(SWD)

Operator: OKMAR OIL COMPANY County GRAHAM 125.52

Name & Address 970 4th FINANCIAL CENTER WICHITA, KANS. 67202 Well Total Depth 3862 feet

ROBERT M. BEREN Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 258'

Abandoned Oil Well Gas Well Input Well X KCoals SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B.J. TITAN License Number

Address BOX 27 OAKLEY, KANS.

Company to plug at: Hour: 1:00 PM Day: 5th Month: Feb. Year: 1986

Plugging proposal received from GEORGE JORGENSEN

(company name) OKMAR OIL COMPANY (phone) 316-265-3311

were: 8 5/8" - 258' SP. CUC 1/175 SK CNT, 4 1/2" CSG SET @ 3860' 1/950 SK CNT, (CMT TO 200)

PBTD-3833' PERFS 3623-38 3657-65 - CEMENT IN ANNULUS BETWEEN 8 5/8" + 4 1/2" UP TO 200 FT.

TUBING AND SOME JUNK IN 4 1/2" CSG. - OPERATOR SAID HOLE OPEN.

RECOMMEND - 400 SK 60/140 FORMIX 6% GEL 3% CACL - 2 SK CELLO FLAKE - AND 4 SK HULLS, AND 4 1/2" PLUG

LOAD AND PRESSURE ANNULUS WITH CEMENT, LOAD AND PRESSURE 4 1/2" CSG

WITH CEMENT. Plugging Proposal Received by Marion Schmidt (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:00 PM Day: 5th Month: FEB Year: 1986

ACTUAL PLUGGING REPORT ORDERED 400 SK 60/140 FORMIX 6% GEL 3% CACL - 2 SK CELLO FLAKE - 4 HULLS + PLUG

PUMPED IN ANNULUS BETWEEN 8 5/8" S.P. AND 4 1/2" CSG. 1/5 SK CMT. MAX.

PRESSURE 600 PSI.G, SHUT IN @ 600 PSI.G.

PUMPED IN 4 1/2" CSG 1/130 SK CMT 1/2 SK CELLO FLAKE - MAX. PRESSURE 2,000 PSI.G

SHUT @ 2000 PSI.G. CEMENTED BY B.J. TITAN

Remarks: (if additional description is necessary, use BACK of this form.)

NOTICED

RECEIVED STATE CORPORATION COMMISSION Signed

Marion Schmidt (TECHNICIAN) DOIC

4 1-13-86

DATE FEB 14 1986

FEB 14 1986 2-14-86 APR

8 1986

INV. NO. 12599 MAR 07 1986

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84