

6 070447

PLUGGED

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NW 1/4, SEC. 8, T. 9 S, R. 23 W

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245 5364
Beren Corporation

Lease Name STEWART Well # 1

Operator Name & Address: OMMAR OIL COMPANY

County GRAHAM 127.56

Address: 970 4th FINANCIAL CENTER
WICHITA, KANSAS. 67202

Well Total Depth 2925 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size _____ feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. TITAN License Number _____

Address BOX 27 OAKLEY, KANSAS.

Company to plug at: Hour: 4:00 PM Day: 5th Month: FEB Year: 19 86

Plugging proposal received from GEORGE JORGENSEN

(company name) OMMAR OIL COMPANY (phone) 316-265-2311

were: 8 5/8" - 250 FT SP. CUL ^{SK} @ 175 CMT, 4 1/2" CSG. SET @ 2922 FT ^{SK} @ 225 CMT.

SQUEEZED 4 1/2" CSG @ 1775 FT ^{SK} @ 250 CMT, @ 2165 FT ^{SK} @ 150 CMT, @ 2024 FT ^{SK} @ 120 CMT.

TESTS @ 3718 - 21 - 3728 - 31 - 3856 - 59, OPERATOR SAID HOLE IS OPEN

RECOMMEND 300 ^{SK} CMT ^{60%} 40 FORMIX ^{6% GEL} 3% CA-CL - 11 ^{SK} GEL; 5 ^{SK} HULLS AND 4 1/2" PLUG.

LOAD AND PRESSURE ANNULUS WITH CEMENT, LOAD AND PRESSURE 4 1/2" CSG WITH CMT.

Plugging Proposal Received by Marion Schmidt
BOIK (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 PM Day: 5th Month: FEB Year: 19 86

ACTUAL PLUGGING REPORT ORDERED 300 ^{SK} 60% 40 FORMIX ^{6% GEL} 3% CA-CL - 11 ^{SK} GEL; 5 ^{SK} HULLS + PLUG.

PUMPED IN ANNULUS 150 ^{SK} CMT ¹ HULLS, MAX PSIG 500, SHUT IN @ 250 PSIG.

PUMPED IN 4 1/2" CSG ¹ 50 ^{SK} CMT ¹ HULLS, 1500 PSIG, FOLLOWED ¹ 50 ^{SK} CMT.

6 ^{SK} PSI.G, THEN 6 ^{SK} GEL, RELEASED PLUG AND 10 ^{SK} CMT, PRESSURED

TO 2500 PSIG, SHUT IN @ 2500 PSIG

CEMENTED BY BJ. TITAN

Remarks: _____
(If additional description is necessary, use BACK of this form.)

NOTICED (copy and not) observe this plugging (VED)
STATE CORPORATION COMMISSION
2-14-86 Signed Marion Schmidt
FEB 14 1986 BOIK (TECHNICIAN)

FEB 14 1986 APR 8 1986 MAR 07 1986 CONSERVATION DIVISION
Wichita, Kansas

5-13-86
MPR