

15-065-03115-00-00  
7-10

71  
R

# 4- 031718

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1959

SW SE SW /4 SEC. 08 , 09 S, 23 W  
330 feet from S section line  
3630 feet from E section line

Operator license# -

Lease Steward well # D-2

Operator: State of Kansas - Fee Fund

County Graham

Address: Evergreen Project  
\_\_\_\_\_  
\_\_\_\_\_

Well total depth 3880 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 276 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Titan License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 10 Month: July Year: 92

Plugging proposal received from: Carl Goodrow

Company: State P.I.R.T. II Phone: \_\_\_\_\_

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Shots @ 1900' and 1100'. Critical shot areas.  
Hole open and dry to perf's.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:50A.M., Day: 10, Month: July, Year: 92

Actual plugging report: 8 5/8" set @ 276' cwc. 4 1/2" set @ 3875'  
with N/A. Perf's 3674' - 3678'. Squeeze 4 1/2" with 300 sx. cement  
blend with 300# hulls mixed in to Max. P.S.I. 800#. Close in P.S.I.  
500#. Backside circulated shut in with Max. P.S.I. 800#. Close in  
P.S.I. 500#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1992

7-17-92  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES  , CALC. \_\_\_\_\_ , NO \_\_\_\_\_ Dakota plug: YES  , NO   
Plugged through TUBING \_\_\_\_\_ , CASING  . Elevation: \_\_\_\_\_ GL

I did[  ] / did not[  ] observe the plugging. Carl Goodrow

(agent)