

To: 6 030564
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447Operator: CITIES SERVICE OIL & GAS CORP.Name & Address 800 SUTTON PLACE BLDG.209 E. WILLIAMWICHITA, KANSAS 67202API NUMBER 15- 10-17-69NW, SEC. 9, T. 9 S, R 23 W4130' feet from S section line3941' feet from E section lineLease Name BRUSH CREEK ^{UNIT} Well 1205-SCounty GRAHAM 64.61Well Total Depth 1988' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size NONE feet 0

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated WATER Supply WELLPlugging Contractor ALLIED CEMENT CO. License Number _____Address BOX 342 PLAINVILLE, KANSAS 67663Company to plug at: Hour: PM Day: 11 Month: 9 Year: 19 85Plugging proposal received from RICK(company name) CITIES SERVICE (phone) _____were: 7" CASING SET @ 1988 W/450 SX. PERFS 1202'-1317 1630-1730FISH @ 1608' CANNOT FISH. HOLE TAKING FLUID. ORDER 200 SX. 60/40POZ 6% GEL 3% CC 5 SX. HULLS ALLIED CMT. CO. OWS WATER TRUCK.15 SX. GEL.Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)Plugging Operations attended by Agent?: All X Part _____ None _____Operations Completed: Hour: 3:PM Day: 11 Month: 9 Year: 19 85ACTUAL PLUGGING REPORT RUN TUBING (2 7/8") TO FISH. MIX. AND PUMP DOWNTUBING 130 SX. CMT. MIX + 3 SX. HULLS LAY DOWN TUBING TO 800' MIX.AND PUMP DOWN TUBING 12 SX. GEL. LAY DOWN TUBING TO 120' MIX ANDPUMP 20 SX. CMT. MIX. CWC. LAY DOWN TUBING HOOK UP SWEDGE TO7" PUMP DOWN 7" WITH 25 SX. CMT. MIX. MAX. PSI 500* CLOSE IN150 PSI Plug completeRemarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 17 1985INV. NO. 10109RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1985

9-16-85

CONSERVATION DIVISION
Wichita, KansasSigned Carl Goodnow
(TECHNICIAN)