

4-032178

Amended 05/22/98
Herb Deines

(Never Permitted)

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 03-25-71

NW NW SE _____ /4 SEC. 11, 09, 23 W
2310 _____ feet from S section line
2310 _____ feet from E section line

Operator license# - _____

(Formerly Jones A-1)
Lease: Jones "OWWO" Well # 1

Operator: State of Kansas Fee Fund

County: Graham

Address: 2301 E. 13th Street
Hays, Kansas 67601
Control No: 970120

Well total depth 3857 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

Aband. oil well _____, Gas well _____, Input well SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# - _____

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 25 Month: September Year: 1996

Plugging proposal received from: Carl Goodrow - District #4 Staff

Company: State of Kansas Phone: 913-628-1200

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Order sand and common cement.

RECEIVED
KANSAS CORP COM
1998 JUN - 3 12:33
6-3-98

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 11:40 A.M., Day: 25 Month: September Year: 1996

Actual plugging report: 8 5/8" set at 160' w/130 sxs cwc. 5 1/2" set at 3856' w/125 sxs.
Prod. Perf 3792' - 3798'. Bridge at 350' - couldn't break through with bailer. Loaded hole
with water, pumped through bridge - fluid fell. Mixed and pumped down 5 1/2" 200 sxs cement
blend with 500# hulls. Circulated cement in 8 5/8" to Max. P.S.I. 800#. Held. Plug
complete.

Remarks:
Condition of casing(in hole): GOOD _____ BAD _____ Any plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not [] observe the plugging.

Carl Goodrow
(agent)

10