

4-032179

Amended 05/22/98
Herb Deines

C-14,679

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 04-16-70

SW SE NE /4 SEC. 11, 09, 23 W
2970 feet from S section line
990 feet from E section line

(Formerly Beckett #3)

Lease: Jones "OWWO" Well # 4

Operator license# -

County: Graham

Operator: State of Kansas Fee Fund

Well total depth 3830 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 212 feet

Address: 2301 E. 13th Street
Hays, Kansas 67601
Control No: 970121

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 25 Month: September Year: 1996

Plugging proposal received from: Carl Goodrow - District #4 Staff

Company: State of Kansas Phone: 913-628-1200

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Order sand and common cement.

RECEIVED
KANSAS CORP COM
JUN 3 1998

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:30 A.M., Day: 25 Month: September Year: 1996

Actual plugging report: 8 5/8" set at 212' w/N/A sxs cwc. 5 1/2" set at 3818' w/300 sxs.
Prod. Perf 3768' - 3775'. Casing bad. Bridge in hole at 830'. Decided not to pull casing.
Ran bailer through plug. Mixed and pumped down 5 1/2" with 200 sxs cement blend with 500#
hulls. Cement circulated in 8 5/8". Pressured-up to Max. P.S.I. 1000#. Held. Plug
complete.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 03 1998

6-3-98

Remarks:
Condition of casing (in hole): GOOD BAD CONSERVATION DIVISION
Bottom plug (in place): YES, CALC, NO ANNY plug: YES X NO
Plugged through TUBING, CASING. Elevation: Dakota plug: YES X, NO

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)