

API NUMBER 15-065-21, 785-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW-NW-SW, SEC. 6, T10S, R22W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1650 FEET FROM N/S SECTION LINE
330 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT
OPERATOR LICENSE # 5900

LEASE NAME G. STITES WELL # 1

OPERATOR: LABANCO DRILG. INC.
NAME & ADDRESS BOX 289
NATOMA, KANS.
67651

COUNTY GRAHAM
WELL TOTAL DEPTH 4156 \$ 135.07 FEET
CONDUCTOR PIPE: SIZE _____ FEET
SURFACE CASING: SIZE 8 5/8 FEET 285

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR LABANCO DRILG. INC. LICENSE NUMBER 458

ADDRESS BOX 289 NATOMA, KS. 67651

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 22ND MONTH: JULY YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM JOHN WIEIS

(COMPANY NAME) LABANCO DRILG. (PHONE) _____

WERE: 8 5/8" - 285 FT SB. CUC #170ST COMMON - 2% GEL - 3% CA-CL. (BY FINED CMT)
ORDER 200ST 5/50 FORMIX 6% GEL. 3% CA-CL. AND 8 5/8" PLUG
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUG
ABUCKLE @ 4136 - ELV. 2372 - ANH. 1932

PLUGGING PROPOSAL RECEIVED BY [Signature]
(TECHNICIAN) DOIC

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 12:15 DAY: 22ND MONTH: JULY YEAR: 1983

ACTUAL PLUGGING REPORT _____

ORDERED 200ST 5/50 FORMIX 6% GEL - 3% CA-CL. AND 8 5/8" PLUG
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUG.
1ST PLUG @ 4110 #1/20 CMT. - 2ND PLUG @ 1950 #1/20ST CMT.
3RD PLUG @ 1080 FT #1/100ST CMT., 4TH PLUG @ 300 FT #1/40ST CMT.
5TH PLUG ^{SOLID BRIDGE} MUD'S + PLUG @ 40 FT #1/10ST CMT.

REMARKS: 10ST CMT IN RAT HOLE (CIRCULATE)

RECEIVED
STATE CORPORATION COMMISSION
08-01-1983
AUG 01 1983

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED [Signature]
(TECHNICIAN) DOIC

INVOICED
DATE 8-5-83
INV. NO. 5059-W

FORM CP-2/3
REV. 6-83