

6 030857

~~03-20-1987~~
MAR 10 1987
API NUMBER 13-

15-065-21175-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CN/2 SE SW, SEC. 7, T 10 S, R 22 W

990 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107

Lease Name Turner Well # 1

Operator: H-30 DRILLING INC.

County Graham 137.44

Name & Address 251 N. WATER ST. 10

Well Total Depth 4229' feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 218'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON SERVICES License Number _____

Address HAYS KANSAS 67601

Company to plug at: Hour: PM Day: 10 Month: 3 Year: 19 87

Plugging proposal received from Jeff Burk

(company name) H-30 (phone) _____

were: 8 5/8 SET @ 218' 4/160 SX. 5 1/2" SET @ 4235 NA BAD CASING 1400' TO 1500'
CASING COLLAPSED @ 1450' TEST SHOWED HOLES @ 1450' ± ORDERED 200 SX.
ECONOLITE 65/35 PZ 10% GEL 2% DICEL 5% HULLS HALLIBURTON CNT. CO.
RUSH WATER TRUCKS. FLUID LEVEL @ 200' OFF BOTTOM

Plugging Proposal Received by Carl Goodlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:45 PM Day: 10 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT MIX & PUMP DOWN 5 1/2" 10 bbl SLURRY (20 SX) 4 SX.

HULLS IN WITH 50 bbl SLURRY (100 SX.) PRESSURE TO 800* PSZ CLOSE IN 500*

MIX & PUMP DOWN 8 5/8" - 5 1/2" ANNULUS 25 bbl SLURRY (50 SX) + HULL PRESSURE

TO 300* CLOSE IN @ 250* PLUG COMPLETE

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

DATE 3-23-87

Signed Carl Goodlow (TECHNICIAN)

STATE CORPORATION COMMISSION

INV. NO. 16388

MAY 14 1987 JUL 08 1987

03-20-1987
CONSERVATION DIVISION 2/3
Wichita, Kansas 01-84

DB