


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-065-00582-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 7 Twp. 10 Rge. 22 (E) W (W)

Location as "NE/CNW&SW" or footage from lines SE NE SW

Lease Owner Kimbark Exploration Co.

Lease Name McVey #1 Well No.

Office Address Denver, Colorado

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5-4-60 19

Plugging completed 5-8-60 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Fabricius

Producing formation Depth to top Bottom Total Depth of Well 3920' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	191'	none
				4-1/2"	3918'	3244'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3920' and found it open.
Filled w/sand to 3850' and dumped 3 sacks of
cement with bailer. Pulled 4 1/2" casing.
Cleared hole and mudded the hole to 190',
set rock bridge to 180' and dumped 25 sacks
of cement. Mudded the hole to 40', set rock
bridge to 30' and ran 10 sacks of cement to
base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1960

05-23-1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.

I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1960

My commission expires

9-27-62

Thomas V. Rupp

Notary Public.



15-065-00582-00-00

MCVEY #1 WELL LOG

LOCATION: SE NE SW SECTION 7
T-10-S, R-22-W
GRAHAM COUNTY, KANSAS

SPUDED: 6/12/58
COMPLETED: 6/23/58

OWNER: THE KIMBARK COMPANY
P. O. Box 1557
DENVER 1, COLORADO

CONTRACTOR: LOGAN DRILLING COMPANY
P. O. Box 1557
DENVER 1, COLORADO

SURFACE CASING: 8-5/8" SS CASING CEMENTED AT 190' K.B. W/125 SACKS POZMIX W/2% CACL.
OIL STRING: 4 1/2", 9.5# J-55 SS CASING CEMENTED AT 3918' W/150 SACKS POZMIX. BAKER
STAGE COLLAR AT 1776 AND CIRCULATED 100 BBLS KEM PACK OIL BASE MUD
BEHIND PIPE TO SURFACE.

LOG

FIGURES INDICATE BOTTOM OF FORMATION.

195	SAND AND SHALE
950	SHALE
1375	SHALE AND SAND
1785	SHALE AND SAND
1935	SHALE
1975	ANHYDRITE
1985	SHALE AND LIME
2275	SHALE AND LIME
2440	SHALE AND LIME
2570	LIME
2660	LIME AND SHALE
2780	LIME AND SHALE
2880	SHALE AND LIME
2940	SHALE AND LIME
3105	LIME AND SHALE
3185	SHALE
3240	SHALE AND LIME
3405	LIME
3505	LIME
3570	SHALE AND LIME
3696	LIME
3723	LIME
3810	LIME
3855	LIME
3870	LIME
3920	SHALE AND LIME

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1960
06-21-1960
CONSERVATION DIVISION
Wichita, Kansas

~~3920~~ ROTARY TOTAL DEPTH

THE UNDERSIGNED, WALTER K. ARBUCKLE, PRESIDENT OF LOGAN DRILLING COMPANY, HEREBY CERTIFIES THAT THE ABOVE IS A TRUE AND CORRECT LOG OF THE FORMATIONS ENCOUNTERED IN DRILLING THE MCVEY #1 AS SHOWN IN THE DAILY DRILLING REPORTS.

Walter K. Ar buckle
WALTER K. ARBUCKLE

STATE OF COLORADO |
CITY & COUNTY OF DENVER |

BE IT REMEMBERED, THAT ON THIS 25TH DAY OF AUGUST A.D. 1958, BEFORE ME *Walter K. Ar buckle*, A NOTARY PUBLIC, PERSONALLY APPEARED WALTER K. ARBUCKLE, PRESIDENT OF LOGAN DRILLING COMPANY, A COLORADO CORPORATION, WHO IS PERSONALLY KNOWN TO ME AND KNOWN TO ME TO BE THE PRESIDENT OF SAID CORPORATION, AND THE SAME PERSON WHO EXECUTED THE FOREGOING INSTRUMENT, AND HE DULY ACKNOWLEDGED THE EXECUTION OF THE SAME FOR AND ON BEHALF OF AND AS THE ACT AND DEED OF SAID CORPORATION.

WITNESS MY HAND AND OFFICIAL SEAL.

MY COMMISSION EXPIRES *August 20, 1960*.

Walter K. Ar buckle
NOTARY PUBLIC