


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

GRAHAM County, Sec. 7 Twp. 10 Rge. (E) 22(W)
Location as "NE/CNW/SW" or footage from lines NW SW SE
Lease Owner THE KIMBARK COMPANY
Lease Name ORAN Well No. 1
Office Address 300 FILLMORE STREET, DENVER 6, COLORADO
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 1/10 19 59
Application for plugging filed 1/10 19 59
Application for plugging approved 1/10 19 59
Plugging commenced 1/10 19 59
Plugging completed 1/10 19 59
Reason for abandonment of well or producing formation DRY



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. D. FABRICIUS
Producing formation Depth to top Bottom Total Depth of Well 4081 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
HEAVY MUD FROM T.D. TO 600'. 20 SACKS CEMENT PLUG FROM 600' TO 535'. MUD FROM 535' TO 190'. 20 SACKS CEMENT PLUG FROM 190 TO 125'. MUD FROM 125' TO 10'. 10 SACKS CEMENT IN TOP OF SURFACE PIPE.

RECEIVED
STATE CORPORATION COMMISSION

FEB 2 1959
02-02-1959
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LOGAN DRILLING COMPANY
Address 300 FILLMORE STREET, DENVER 6, COLORADO


STATE OF COLORADO, COUNTY OF DENVER, ss.
W. K. ARBUCKLE (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. K. Ar buckle*
W. K. ARBUCKLE
P. O. Box 1557, DENVER 1, COLORADO
(Address)

SUBSCRIBED AND SWORN to before me this 22ND day of JANUARY, 19 59

Sue B. Thompson

Notary Public.



PLUGGING
FILE SEC 7 T. 10 R. 22W
BOOK PAGE 11 LINE 29

15-065-02645-00-00

ORAN #1 WELL LOG

LOCATION: NW SW SE SECTION 7
T-10-S, R-22-W
GRAHAM COUNTY, KANSAS

SPUDDED: 12/30/58
COMPLETED: 1/10/59

OWNER: THE KIMBARK COMPANY
P. O. Box 1557
DENVER 1, COLORADO

CONTRACTOR: LOGAN DRILLING COMPANY
P. O. Box 1557
DENVER 1, COLORADO

SURFACE CASING: 8-5/8" SS CASING CEMENTED AT 194' K.B. w/130 SX.

OIL STRING: NONE

LOG

FIGURES INDICATE BOTTOM OF FORMATION.

200	SAND AND SHALE
970	SHALE
1630	SHALE
1930	SHALE AND SAND
1960	ANHYDRITE
1980	ANHYDRITE
2160	SHALE
2415	SHALE
2520	LIME AND SHALE
2650	LIME AND SHALE
2715	LIME
2745	SHALE AND LIME
2950	LIME
3025	SHALE AND LIME
3080	LIME AND SHALE
3220	SHALE AND LIME
3315	LIME AND SHALE
3400	SHALE AND LIME
3505	SHALE AND LIME
3585	LIME AND SHALE
3670	SHALE AND LIME
3715	SHALE AND LIME
3775	LIME
3825	LIME
3865	LIME
3915	LIME
3920	LIME
3995	SHALE AND CHALK
4030	LIME AND CHERT
4076	LIME
4081	LIME
4081	ROTARY TOTAL DEPTH

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1959
CO. 01-28-1959
WILLIAM, KANSAS

THE UNDERSIGNED, W. K. ARBUCKLE, PRESIDENT OF THE LOGAN DRILLING COMPANY, HEREBY CERTIFIES THAT THE ABOVE IS A TRUE AND CORRECT LOG OF THE FORMATIONS ENCOUNTERED IN DRILLING THE ORAN #1 AS SHOWN IN THE DAILY DRILLING REPORTS.

LOGAN DRILLING COMPANY

W. K. Arbuckle
W. K. ARBUCKLE, PRESIDENT

PLUGGING
FILE SEC. 7 T. 10 R. 22 W
BOOK PAGE 11 LINE 29

STATE OF COLORADO
CITY & COUNTY OF DENVER

BE IT REMEMBERED, THAT ON THIS 16th DAY OF January A.D., 1959, BEFORE ME *W. B. Thompson*, A NOTARY PUBLIC PERSONALLY APPEARED W. K. ARBUCKLE, PRESIDENT OF LOGAN DRILLING COMPANY, A COLORADO CORPORATION, WHO IS PERSONALLY KNOWN TO ME AND KNOWN TO ME TO BE THE PRESIDENT OF SAID CORPORATION, AND THE SAME PERSON WHO EXECUTED THE FOREGOING INSTRUMENT, AND HE DULY ACKNOWLEDGED THE EXECUTION OF THE SAME FOR AND ON BEHALF AND AS THE ACT AND DEED OF SAID CORPORATION.

WITNESS MY HAND AND OFFICIAL SEAL.

MY COMMISSION EXPIRES April 17, 1962.

W. B. Thompson
NOTARY PUBLIC.